



Table 3.1: Elevator Shaft Inspection Summary

LCD No. 2372-572
BOE Assessment

Elevator Shafts	Elevator Car	Approx. Total Inspected Areas per Shaft (square feet)	Approx. Areas with Visible Mold Growth per Shaft (square feet)	Percent of Areas with Visible Mold Growth	Number of Inspected Panels per Shaft	Number of Panels with Water Staining
1 Low Rise	1	12,636	1	0.01%	468	65
	2					
2 Low Rise/ High Rise	3	44,928	16	0.04%	1,664	108
	4					
	5					
	6					
3 High Rise	7	46,332	137	0.30%	1,716	171
	8					
	9					
4 Freight	10	15,444	1	0.01%	572	25
5 Parking Structure	11	3,456	0	0.00%	128	38
	12					
6 Parking Structure	13	3,456	0	0.00%	128	0
	14					
Totals		126,252	155	0.12%	4,676	407

Note: Although panels may vary in size due to adjustments made during installation, the average panel is approximately 27 square feet.